Reviewed for code compliance
with IRC 2015
Kitsap County Building Department
GShapiro@co.kitsap.wa.us
04/14/2020

BASIC PERMIT PACKAGE
REVIEWED FOR CODE COMPLIANCE
WITH IRC 2015
KITSAP COUNTY BUILDING DEPARTMENT

Window, Skylight and Door Schedule

Project Information

2322 Basic
Establish Basic Plan
Port Orchard, WA 98367

Contact Information

Disney and Associates
5706 Bethel Road SE Suite 100
Port Orchard, WA 98367

Subject To Field Inspection

	Ref.	U-factor	Qt.	Width Feet	Width Inch	Height Feet	Height Inch	Area	UA
Exempt Swinging Door (24 sq. ft. max.)								0.0	0.00
Exempt Glazed Fenestration (15 sq. ft. max.)								0.0	0.00

Vertical Fenestration (Windows and doors)

Component Description	Ref.	U-factor	Qt.	Width Feet	Width Inch	Height Feet	Height Inch	Area	UA
5650 fx temp lowe argon	JeldWe	0.28	1	5	6	5	0	27.5	7.70
16x16 fx lowe argon	JeldWe	0.28	1	0	16	0	16	1.8	0.50
3046 lowe argon	JeldWe	0.28	1	3	0	4	6	13.5	3.78
2650 sh temp lowe argon	JeldWe	0.28	1	2	6	5	0	12.5	3.50
2040 sh temp lowe argon	JeldWe	0.28	1	2	0	4	0	8.0	2.24
9" sl temp lowe argon	JeldWe	0.28	1	0	9	8	0	6.0	1.68
3050 sh lowe argon	JeldWe	0.28	2	3	0	5	0	30.0	8.40
5050 fx temp lowe argon	JeldWe	0.28	1	5	0	5	0	25.0	7.00
5026 fx temp lowe argon	JeldWe	0.28	1	5	0	2	6	12.5	3.50
6060 sl temp lowe argon	JeldWe	0.28	2	6	0	6	0	72.0	20.16
2660 fx temp	JeldWe	0.28	3	2	6	6	0	45.0	12.60
6080 sl gl dr ox temp lowe argon	JeldWe	0.28	2	6	0	8	0	96.0	26.88
8080 sl gl dr ox temp lowe argon	JeldWe	0.28	1	8	0	8	0	64.0	17.92
6018 fx temp lowe argon	JeldWe	0.28	1	6	0	1	8	10.0	2.80
4050 sl temp lowe argon	JeldWe	0.28	1	4	0	5	0	20.0	5.60
6050 sl temp lowe argon	JeldWe	0.28	2	6	0	5	0	60.0	16.80
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00

Established Basic Permit #

19-05700

CHANGES
MUST Be Approved Prior
To Performing Work

Permit Number: **20-00762**

									0.0	0.00
									0.0	0.00
									0.0	0.00
									0.0	0.00
									0.0	0.00
									0.0	0.00
									0.0	0.00

Sum of Vertical Fenestration Area and UA	503.8	141.06
Vertical Fenestration Area Weighted U = UA/Area		0.28

Overhead Glazing (Skylights)

Component Description	Ref.	U-factor	Qt.	Width Feet	Width Inch	Height Feet	Height Inch	Area	UA
Lowe3 argon filled dbl glazed temp	Velux	0.49	1	4	0	4	0	16.0	7.84
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00
								0.0	0.00

Sum of Overhead Glazing Area and UA	16.0	7.84
Overhead Glazing Area Weighted U = UA/Area		0.49

Total Sum of Fenestration Area and UA ***(for heating system sizing calculations)*** 519.8 148.90

Established Basic Permit #

19-05700

Permit Number: **20-00762**